	Description	Unit	App Qty	Approved Rates of	
				Rate in figures	Rate in words
	COMMON SERVICE PANEL INCOMER : 125A 4P MCCB WITH ACCESSORIES OUTGOINGS : 63A TPN MCB 40A DP MCB BUSBAR & FABRICATION : 125A CAPACITY AL. BUSBAR WITH HEAT SHRINKABLE SLEEVES PANEL FABRICATION WITH 14/16 SWG CRCA SHEET SIEMENS GREY POWDER COATED PANEL	Set	1.00	68000.00	Rupees Sixty Eight Thousand Only
	APFC PANEL (60kVAR) INCOMER : 200A TPN MCCB WITH ACCESSORIES APFC RELAY (6 STAGE) AUTO MANUAL SEL. SWITCH RYB LED INDICATING LAMPS WITH MCB OUTGOINGS : 63A TP MCB 32A TP MCB 16A TP MCB 25kVAR CAP. DUTY CONT 10kVAR CAP. DUTY CONT 5kVAR CAP. DUTY CONT 25kVAR CAPACITOR 10kVAR CAPACITOR 5kVAR CAPACITOR ON OFF ILPB BUSBAR & FABRICATION : 200A CAPACITY AL. BUSBAR WITH HEAT SHRINKABLE SLEEVES PANEL FABRICATION WITH 14/16 SWG CRCA SHEET SIEMENS GREY POWDER COATED PANEL	Set	1.00	100000.00	Rupees One Lakh(s) Only
	Supplying, fixing, wiring, earth electrode for grounding conduits, I.C. cutouts and other equipment's on the meter board using 40mm dia 2.90mm thick GI pipe 2.5 mtr long buried in a pit ... The pit should be filled with equal proportion of salt and charcoal 150mm all-round the pipe to complete depth. The connection from the pipe to the conduit etc., is to be established through GI wire of size as per ISI specification 7.3.3. of IS 732 using 12mm dia bolts, nuts, washers and check nuts etc., the pipe shall have 16 through holes of 122 mm dia.with all lead and lift and directions of the Engineer-In-charge of the work	No	10.00	3000.00	Rupees Three Thousand Only
	Supplying fixing and wiring earth electrode for grounding of lifts, transformers, DG Set etc. using 40mm dia 2.9mm thick 2.5 mtr long GI pipe with GI funnel with mesh and suitable size reducer fixed on the top of the earth electrode. The funnel should be enclosed in a CC chamber of 400x400x400mm with a cast iron cover. The earth electrode shall have staggered holes of 12mm dia and the electrode should be covered 150mm all-round with alternate layers of salt and charcoal from the bottom of the CC chamber. The connection from the electrode is to be established through GI strip using GI bolts and nuts.with all lead and lift and directions of the Engineer-In-charge of the work	No	8.00	4500.00	Rupees Four Thousand Five Hundred Only
	Supplying and running of GI/Copper strips for grounding connections, using necessary fixing materials as required. GI strip.with all lead and lift and directions of the Engineer-In-charge of the work 25x6mm	Mtr	500.00	125.00	Rupees One Hundred Twenty Five Only
	40x6mm	Mtr	75.00	180.00	Rupees One Hundred Eighty Only
	600x600x3mm GI Plate	Each	8.00	800.00	Rupees Eight Hundred Only

Executive Engineer,
Project Division, Yelahanka

Sl. No	Description	Unit	App Qty	Approved Rates of	
				Rate in figures	Rate in words
272	Supplying and running of GI/Copper strips for grounding connections, using necessary fixing materials as required. 25x3mm Copper strip.with all lead and lift and directions of the Engineer-In-charge of the work 25x3mm	Mtr	75.00	550.00	Rupees Five Hundred Fifty Only
273	600x600x3mm plate	Each	6.00	7250.00	Rupees Seven Thousand Two Hundred Fifty Only
274	Supplying of 1.1 KV LT UG cable having aluminum conductor PVC insulated, extruded inner sheathed, galvanized, steel strip (except 2CX10Sq.mm wire armoured) confirming to IS-3975:1990 (No. of Strip indicated in GTP) & extruded PVC outer sheathed armoured cable with specified IS-1554 Part-1:1988 & confirming to GTP of GROUP-A.with all lead and lift and directions of the Engineer-In-charge of the work 2 core 10 sqmm	Mtr	650.00	95.00	Rupees Ninety Five Only
275	4 core 10 sqmm	Mtr	650.00	135.00	Rupees One Hundred Thirty Five Only
276	4 core 16 sqmm	Mtr	950.00	150.00	Rupees One Hundred Fifty Only
277	3.5 core 25 sqmm	Mtr	120.00	180.00	Rupees One Hundred Eighty Only
278	3.5 core 50 sqmm	Mtr	280.00	300.00	Rupees Three Hundred Only
279	3.5 core 70 sqmm	Mtr	25.00	300.00	Rupees Three Hundred Only
280	3.5 core 240 sqmm	Mtr	100.00	1250.00	Rupees One Thousand Two Hundred Fifty Only
281	Labour charges for laying of 1.1 KV class UG cable in existing trench GI pipe / stoneware pipe / on wall / on pole as required.In existing trench/duct.with all lead and lift and directions of the Engineer-In-charge of the work 6 sqmm to 16 sqmm	Mtr	2250.00	15.00	Rupees Fifteen Only
282	25 sqmm to 75 sqmm	Mtr	425.00	20.00	Rupees Twenty Only
283	95 sqmm to150Sqmm	Mtr	100.00	30.00	Rupees Thirty Only
284	Digging of trench of 0.6m deep x 0.50 mtr wide refilling the trench to the required ground level and consolidating etc., complete.(As per Civil SR KSRB I-2, P-7) In soil (ordinary) with all lead and lift and directions of the Engineer-In-charge of the work	Mtr	100.00	85.00	Rupees Eighty Five Only
285	Supplying and fixing of heavy duty cable glands suitable for UG cable of 1.1 KV class (metal only) with all lead and lift and directions of the Engineer-In-charge of the work 25mm dia	Each	60.00	95.00	Rupees Ninety Five Only
286	32mm dia	Each	8.00	150.00	Rupees One Hundred Fifty Only
287	45mm dia	Each	2.00	250.00	Rupees Two Hundred Fifty Only
288	63mm dia	Each	14.00	500.00	Rupees Five Hundred Only
289	Supplying and fixing 2mm thick perforated cable tray with powder coated paint on existing MS angle support using necessary GI bolts/nuts and washer or welding as required.750x50mm with all lead and lift and directions of the Engineer-In-charge of the work	Mtr	50.00	1250.00	Rupees One Thousand Two Hundred Fifty Only
290	Supplying tinned copper lugs and crimping and wiring to terminal point for wire of the following sizes.with all lead and lift and directions of the Engineer-In-charge of the work 10 sqmm	Each	36.00	10.00	Rupees Ten Only
291	16 sqmm	Each	24.00	15.00	Rupees Fifteen Only
292	25 sqmm Long Barrel	Each	2.00	30.00	Rupees Thirty Only
293	50 sqmm Long Barrel	Each	6.00	70.00	Rupees Seventy Only
294	70 sqmm Long Barrel	Each	2.00	150.00	Rupees One Hundred Fifty Only
295	150 sqmm Long Barrel	Each	2.00	260.00	Rupees Two Hundred Sixty Only
296	240 sqmm Long Barrel	Each	14.00	500.00	Rupees Five Hundred Only

Contractor

Executive Engineer,
Project Division, Yelahanka

Sl. No	Description	Unit	App Qty	Approved Rates of	
				Rate in figures	Rate in words
297	Supplying and running GI/Copper conductor for grounding and (along with other wires in conduit system of wiring) using necessary suitable size clamps, nails, guttas/spacers etc. Copper wire.8 SWG.with all lead and lift and directions of the Engineer-In-charge of the work	Mtr	360.00	125.00	Rupees One Hundred Twenty Five Only
298	Supplying exhaust fan of 1440 RPM of 300mm (12") size with bracket blades complete for light duty suitable to operate on 230V 50Hz, AC Supply.with all lead and lift and directions of the Engineer-In-charge of the work	Each	20.00	1850.00	Rupees One Thousand Eight Hundred Fifty Only
299	Supplying capacitor type ceiling fan complete with down rod blades, shackle, canopies etc., for operation on 230 volts, 50 cycles. Single phase AC supply conforming to ISS-374-1979 and with double ball bearing system. 56" Sweep (1400mm) Economy model.with all lead and lift and directions of the Engineer-In-charge of the work	Each	165.00	2200.00	Rupees Two Thousand Two Hundred Only
300	Supplying wall mounting fan suitable to operate at single-phase 230v A.C. supply.400mm Sweep.with all lead and lift and directions of the Engineer-In-charge of the work	Each	25.00	2650.00	Rupees Two Thousand Six Hundred Fifty Only
301	Supplying and drawing UTP-CAT 6E LAN cable.with all lead and lift and directions of the Engineer-In-charge of the work	MT.	600.00	30.00	Rupees Thirty Only
302	Supplying and drawing PVC flexible one pair telephone unarmoured tinned copper cable.2Pair.with all lead and lift and directions of the Engineer-In-charge of the work	Rmt.	2300.00	18.00	Rupees Eighteen Only
303	Supplying and drawing PVC insulated gas injected physical foam jelly flooded co-axial TV cable.RG-6.with all lead and lift and directions of the Engineer-In-charge of the work	Rmt.	500.00	45.00	Rupees Forty Five Only
304	Supplying, erecting, testing & commissioning of OFF-LINE UPS system suitable for operation on 230V, 50Hz, A/C supply, with all accessories complete and Excluding batteries and wiring complete.5 KVA OFF LINE UPS Two Hour back up Excluding 6x 120Ah batteries.with all lead and lift and directions of the Engineer-In-charge of the work	Each	6.00	6000.00	Rupees Six Thousand Only
305	Supplying, installation, testing & commissioning of 12Volts ..AH batteries in poly propylene container for D.G. Set Low maintenance batteries, plate type.120 AH capacity. Acid batteries.with all lead and lift and directions of the Engineer-In-charge of the work	Each	30.00	20000.00	Rupees Twenty Thousand Only
306	Supplying, erection, testing and commissioning of .....KVA Diesel Generating Set on existing CC platform Comprising of Diesel Engine Developing ..... BHP @ 1500 RPM confirming to BS 5514.The engine should be turbocharged, Air/water cooled with 10 % over load for 1hour in every 12 hours of operation coupled to suitable capacity alternator rated at 415V, 0.8 PF(lag) 50 Hz, 3 phase, 4 wire system, confirming to BS 5000/IS 4722. The alternator shall be of brushless type ,Screen protected, revolving field, Mounted on suitable Channel Iron Base Frame, Complete with suitable capacity Fuel Tank, required nos. of Batteries of 12/24V as per requirement, Acoustic enclosure as per CPCB Approved Norms.125kva/100kw.with all lead and lift and directions of the Engineer-In-charge of the work	Each	1.00	900000.00	Rupees Nine Lakh(s) Only

Contractor

Executive Engineer,
Project Division, Yelahanka

Sl. No	Description	Unit	App Qty	Approved Rates of	
				Rate in figures	Rate in words
307	Supply, Erection, testing and commissioning of AMF panel suitable for .....KVA DG Set The panel is of cubical type base/floor mounting control panel with hinged doors, undrilled bottom gland plate, aluminum Bus Bar with the accommodation for .....amps 4 pole contactor for alternator with thermal O/L relay,..... Amps 4 pole contactor for mains, HRC fuse for short circuit protection, Microprocessor based AMF module with supply failure timer, Restoration timer, 3 impulse automatic engine start/stop logic, Mains/generator voltage, ...capacity bypass switch and frequency sensing, PCC 1301 controller with water temperature/Lube oil pressure/ engine speed,(ob Voltage/ampere/Frequency/ KVA, Running-hour count, No of starts, Fault indication, over /under speed, Fails to start, Low oil pleasure, High engine temperature, Under/over voltage, over current, Earth fault relay, with indications for Mains on, Load on Mains, Battery charger on Push buttons AMf module by pass Mode, Battery charger unit with inbuilt Auto/Manual and Flat/Boost facility.(ats switch instead off contractor) 62.5 KVA-125kva.with all lead and lift and directions of the Engineer-In-charge of the work	Each	1.00	140000.00	Rupees One Lakh(s) Forty Thousand Only
308	Filtering of oil in the transformer at the transformer center by hot process using "Stream line filter" such time the dielectric strength of the oil in the transformer conforms to ISI specification [Test certificate to be produced]with all lead and lift and directions of the Engineer-In-charge of the work	Litre	200.00	30.00	Rupees Thirty Only
309	Supplying and Topping -up of new Transil OIL	Per Litre	100.00	200.00	Rupees Two Hundred Only
310	Supplying and filling fresh silica gel to the breather of transformers.	Per breather	1.00	150.00	Rupees One Hundred Fifty Only
311	Supplying and Testing of OIL for Di-Electric strength (BDV) / Acidity	Per Sample	1.00	250.00	Rupees Two Hundred Fifty Only
312	Fixing all types and all capacities of fluorescent / false ceiling / spot light / CFL / LED fittings indoor on the wall / ceiling / rafters / girders using 23/0.0076" twin twisted PVC insulated wires, required Nos of round blocks and clamps.On wall / ceiling / Rafter / Girders.with all lead and lift and directions of the Engineer-In-charge of the work	Each	685.00	125.00	Rupees One Hundred Twenty Five Only
313	Fixing a ceiling / Wall mounting fan of all capacities and all types to the existing 'S' hook with fan regulator to the existing board together with supplying and fixing 5 amps. ceiling rose, necessary length of 23 / 0.0076 inch PVC insulated twin twisted copper wire and wiring.with all lead and lift and directions of the Engineer-In-charge of the work	Each	180.00	150.00	Rupees One Hundred Fifty Only
314	Fixing one exhaust fan in the nitch already left in the wall with bolts and nuts and 5 amps. ceiling rose with sufficient length of 23 / 0.0076 inch PVC insulated twin core wire.with all lead and lift and directions of the Engineer-In-charge of the work	Each	20.00	500.00	Rupees Five Hundred Only
315	Providing Supplying and Commissioning of WASHER EXTRACTOR MAKE : RAMSONS/Equivalent MODEL : RVWE - 45 CAPACITY : 45 Kgs HEATING : ELECTRIC for washing bed linen such as bedsheet,pillow covers and patient gowns Dimension : (1350x1400x1750 mm) with all lead and lift and directions of the Engineer-In-charge of the work	No	1.00	1450000.00	Rupees Fourteen Lakh(s) Fifty Thousand Only
316	Providing Supplying and Commissioning of WASHER EXTRACTOR MAKE : RAMSONS/Equivalent MODEL : RVWE - 10 CAPACITY : 10 Kgs HEATING : ELECTRIC For washing OT / Infected linen Dimension : (930x970x1355 mm) with all lead and lift and directions of the Engineer-In-charge of the work	No	1.00	514000.00	Rupees Five Lakh(s) Fourteen Thousand Only

Contractor

Executive Engineer,
Project Division, Yelahanka

Sl. No	Description	Unit	App Qty	Approved Rates of	
				Rate in figures	Rate in words
317	Providing Supplying and Commissioning of TUMBLE DRIER MAKE : RAMSONS/Equi9valent MODEL : RVWE - 45 CAPACITY : 45 Kgs HEATING : ELECTRIC for drying bed linen such as patient gowns etc.,(1050x1320x1870 mm) with all lead and lift and directions of the Engineer-In-charge of the work	No	1.00	450000.00	Rupees Four Lakh(s) Fifty Thousand Only
318	Providing Supplying and Commissioning of TUMBLE DRIER MAKE : RAMSONS/Equi9valent MODEL : RTD - 15 CAPACITY : 15 Kgs HEATING : ELECTRIC for drying OT/infected linen (830x1270x1490 mm) with all lead and lift and directions of the Engineer-In-charge of the work	No	1.00	360000.00	Rupees Three Lakh(s) Sixty Thousand Only
319	Providing Supplying and Commissioning of FLAT WORK IRONER MAKE : RAMSONS/Equi9valent ROLLER LENGTH : 1600 MM ROLLER DIA: 250 MM HEATING : ELECTRIC for drying bed linen such as bedsheet, pillow covers (830x1270x1490 mm).with all lead and lift and directions of the Engineer-In-charge of the work	No	1.00	650000.00	Rupees Six Lakh(s) Fifty Thousand Only

8/9/17

Executive Engineer,
Project Division, Yelahanka